



MOLA FAKO & SONS CONSTRUCTION COMPANY LTD

SERVICES OFFERED: General Construction, Renovation, Plan Drawing, Consultancy, Site Plan Development, Building Permit and Land Certificate follow up

HEAD OFFICE: Lady L. Street - Untarred Malingo - Molyko – Buea

Tel: (237) 654 992 525/672 259 888

E-Mail: mola

1) Foundation		Bill of Quantity		
Nº	DESCRIPTION	Qty	UNIT PRICE	Amount
01	Nº of Blocks =842	28bags	1800frs	50400frs
02	Rods: 10mm=length	76	4500frs	342000frs
	6mm= length	57	1700frs	96900frs
03	Wire =Bundles	20	8000frs	160,000frs
04	Nails =Pakts	15	4500frs	67,500frs
05	Boards = ¹ / ₁₂	30	6500frs	195,000frs
06	Sand = Trips	4	120,000frs	480,000frs
07	Gravel= (15/25) tons	40	15650frs	626,000frs
08	Cements = Bags	136	4500frs	612,000frs
09	Lat for pecking	30	1800	54,000frs
Material Cost				2,683,800frs
Labour				1,500,000frs
Grand Total				4,183,800

Note: In case of backfilling with additional soil is the responsibility of the site supervisor.



MOLA FAKO & SONS CONSTRUCTION COMPANY LTD

SERVICES OFFERED: General Construction, Renovation, Plan Drawing, Consultancy, Site Plan Development, Building Permit and Land Certificate follow up

HEAD OFFICE: Lady L. Street - Untarred Malingo - Molyko – Buea

Tel: (237) 654 992 525/672 259 888

E-Mail: mola

2) ELEVATION

No	Description	Qty	Unit Price	Amount
1	No of blocks (15x20x40) 3500	40	1800frs	72.000frs
2	Rods 8mm length (F500)	108	3.500frs	378.000frs
	Rod 6mm length	86	1700frs	180.200frs
3	Binding wire (bundles)	35	8000frs	280.000frs
4	Boards (1x12)	30	5.500frs	165.000frs
5	Nails (pkts)	20	4.500frs	90.000frs
6	Sand (tripe)	6	120.000frs	720.000frs
7	Gravel (15/25) tons	40	15650frs	626.000frs
8	Cement (bags)	174	4.500frs	787.500frs
9	Cost of materials			3.298.500frs
	Labour			1.980.200frs
	TOTAL			5.278.700frs



MOLA FAKO & SONS CONSTRUCTION COMPANY LTD

SERVICES OFFERED: General Construction, Renovation, Plan Drawing, Consultancy, Site Plan Development, Building Permit and Land Certificate follow up

HEAD OFFICE: Lady L. Street - Untarred Malingo - Molyko – Buea

Tel: (237) 654 992 525/672 259 888

E-Mail: mola

3) ROOFING

No	Description	Qty	Unit Price	Amount
1	Wood (2x6)	205	4000frs	820.000frs
2	Zinc	380cm	4000frs	1.520.000frs
3	Gutters	17	7.500frs	127.500frs
4	Lining	16	5.000frs	80.000frs
5	Cutting facial board (pieces)	84	2000frs	168.000frs
6	Vally gutter	2	7.500frs	15.000frs
7	Toilise	45cm	3.500frs	157.500frs
8	Power nail (packets)	5	1.500frs	7.500frs
9	Nail (40) (packets)	1	4500frs	5000frs
10	Nail (80, 90, 100) (packets)	13	4.500frs	58.500frs
11	Zinc nail (packets)	8	4000frs	32.000frs
12	Gasket (packets)	24	1000frs	24.000frs
13	Top ridge	15	7.500frs	112.500frs
14	Rabbeting pin (packets)	3	4000frs	12.000frs
15	Belt (pieces)	90	200frs	18.000frs
16	Funnel	8	1000frs	8.000frs
	Cost of material			3.165.000frs
	Labour			450.000frs
	TOTAL			3.615.000frs



MOLA FAKO & SONS CONSTRUCTION COMPANY LTD

SERVICES OFFERED: General Construction, Renovation, Plan Drawing, Consultancy, Site Plan Development, Building Permit and Land Certificate follow up

HEAD OFFICE: Lady L. Street - Untarred Malingo - Molyko – Buea

Tel: (237) 654 992 525/672 259 888

E-Mail: mola

4) ELECTRICAL WORK

FIRST PHASE (1)

S/N	DESCRIPTION	Q'TY	U.P	AMOUNT
1	Conduit pipe 32	1	10,000	10,000
2	Conduit pipe 25	3	14,000	42,000
3	Conduit pipe 20	2	12,000	24,000
4	Square cups	60	300	18,000
5	Main switch	1	15000	15,000
6	Junction box	10	1500	15,000
7	Earth rod	1	12000	12,000
8	Copper wire	20	2000	40,000
Material Cost (1)				176,000
SECOND PHASE (2)				
9	Sucket	25	1000	25,000
10	2 way 2 Gang	10	1000	10,000
11	2 way 1 gang	20	1000	20,000
12	Television sucket	10	1000	10,000
13	Bulb holder	10	1000	10,000
14	Bulbs	10	1500	15,000
15	Cable 2.5 mm	6	22,000	132,000
16	Cable 1.5 mm	8	16,000	128,000
17	T.V Cable	2	20,000	40,000
18	connector	10	2,000	20,000
19	Fuse breaker	10	3,000	30,000
Material Cost (2)				440,000 Frs
Labour (3)				350,000 Frs
Grand Total (1+2+3)				966,000 Frs



MOLA FAKO & SONS CONSTRUCTION COMPANY LTD

SERVICES OFFERED: General Construction, Renovation, Plan Drawing, Consultancy, Site Plan Development, Building Permit and Land Certificate follow up

HEAD OFFICE: Lady L. Street - Untarred Malingo - Molyko – Buea

Tel: (237) 654 992 525/672 259 888

E-Mail: mola

5) CEILING

No	Description	Qty	Unit Price	Amount
1	Lads for knocking (2x2)	120	1.200frs	144.000frs
2	Plywood (sheets)	49	4500frs	220.500frs
3	Nails (packets)	10	4500frs	45.000frs
4	Power nail (packets)	20	1.500frs	30.000frs
	Cost of materials			439.500frs
	Labour			180.000frs
	TOTAL			619.500frs

6) WOOD WORK

No	Description	Qty	Unit Price	Amount
1	Doors frame (pepper wood with fondue applied)	10	21.000frs	210.000frs
2	Shutter (pepper wood with fondue applied)	10	75.000frs	750.000frs
3	Ordinary cement for fitting (bags)	2	4.500frs	9.000frs
	TOTAL			969.000frs

7) METAL WORK

No	Description	Qty	Unit Price	Amount
1	Door (120)	1	100.000frs	100.000frs
	Door (90)	2	85.000frs	170.000frs
2	Window protectors (1.5m)	10	35.000frs	350.000frs
3	Ordinary cement for fitting (bags)	2	4.500frs	9.000frs
	Provisional sum (TOTAL)			529.000frs



MOLA FAKO & SONS CONSTRUCTION COMPANY LTD

SERVICES OFFERED: General Construction, Renovation, Plan Drawing, Consultancy, Site Plan Development, Building Permit and Land Certificate follow up

HEAD OFFICE: Lady L. Street - Untarred Malingo - Molyko – Buea

Tel: (237) 654 992 525/672 259 888

E-Mail: mola

8) TILING

No	Description	Qty	Unit Price	Amount
1	Floor tiles (M ²)	154.86	3.390frs	524.975frs
2	Wall tiles (toilet and kitchen) M2	133.8	3.500frs	468.300frs
3	Ordinary cement (bags)	65	4500frs	292.500frs
4	Cement colle (bags)	100	2500frs	250.000frs
	Cost of Materials			1.535.775frs
	Labour (per M ²)	288.66	2000frs	577.320frs
	TOTAL			2.113.095frs

9) DOCORATION

No	Description	Qty	Unit Price	Amount
1	Provisional sum (General painting) (drums)	15	35000frs	525.000frs

10) PLASTERING

No	Description	Qty	Unit Price	Amount
1	Internal walls (Msq)	309.12	1.500frs	468.680frs
2	External walls (Msq)	138.32	2.000frs	276.640frs
3	Cement (bags)	70	4.500frs	315.000frs
4	Soft sand (trip)	2	120.000frs	240.000frs
	TOTAL			1.300.320frs



MOLA FAKO & SONS CONSTRUCTION COMPANY LTD

SERVICES OFFERED: General Construction, Renovation, Plan Drawing, Consultancy, Site Plan Development, Building Permit and Land Certificate follow up

HEAD OFFICE: Lady L. Street - Untarred Malingo - Molyko – Buea

Tel: (237) 654 992 525/672 259 888

E-Mail: mola

11A) PLUMBING WORK (PIPPING)

No	Description	Qty	Unit Price	Amount
1	Normalize pipe 100	10	4.500frs	45.000frs
2	Normalize pipe 63	10	3.000frs	30.000frs
3	Normalize pipe 40	2	2.000frs	4.000frs
4	PVC TEE100	10	1.500	15.000frs
5	PVC elbow 100	10	1.000frs	10.000frs
6	PVC 45 bend 100	8	1.000frs	8.000frs
7	PVC Y100	12	1.500frs	18.000frs
8	PVC reducer 63/100	15	1.000frs	15.000frs
9	PVC Plug 63	4	500frs	2.000frs
10	PVC Y63	4	600frs	2.400frs
11	PVC TEE 63	10	600frs	6.000frs
12	PVC Pegafor gum (kg)	1.5	10.000frs	15.000frs
13	PVC vein plug 100	3	3.000frs	9.000frs
14	PVC vein plug 63	4	2.000frs	8.000frs
15	Camping gas	4	1.000frs	4.000frs
16	Binding wire	2	1.000frs	2.000frs
17	Clip 100	4	1.000frs	4.000frs
18	Clip 63	6	600frs	3.600frs
19	Peck 10	1	1.500frs	1.500frs
20	Cement (bags)	5	4.500frs	22.500frs
21	Rod 8	3	3.500	10.500frs
	Cost of materials			235.500frs
	Labour			140.000frs
	TOTAL			375.500frs



MOLA FAKO & SONS CONSTRUCTION COMPANY LTD

SERVICES OFFERED: General Construction, Renovation, Plan Drawing, Consultancy, Site Plan Development, Building Permit and Land Certificate follow up

HEAD OFFICE: Lady L. Street - Untarred Malingo - Molyko – Buea

Tel: (237) 654 992 525/672 259 888

E-Mail: mola

11B) PLUMBING WORK (INTERNAL PIPING)

No	Description	Qty	Unit Price	Amount
1	PPR pipe 25	25	4.000frs	100.000frs
2	PPR shower stop valve 25	10	4.000frs	40.000frs
3	PPR female elbow 25	25	600frs	15.000frs
4	PPR male elbow 25 ½ inch	10	600frs	6.000frs
5	PPR female Tee 25 ½ inch	20	600frs	12.000frs
6	PPR plain elbow 25	25	250frs	6250frs
7	PPR plain Tee 25	20	250frs	5.000frs
8	PPR plain socket 25	25	250frs	6.250frs
9	PPR union join 25	15	250frs	3.750frs
10	PPR male adaptor	10	600frs	6.000frs
11	Panaflex join 25	6	1.500frs	9.000frs
12	Panaflex elbow 25	6	1.500frs	9.000frs
13	Panaflex pipe 25 (meters)	15	500frs	7.500frs
14	½ inch plug	10	200frs	2.000frs
15	Camping gas	2	1.000frs	1.000frs
16	Cement (bag)	1	4.500frs	4.500frs
17	Normal stop valve 25	2	2.500frs	5.000frs
	Cost of materials			238.250
	Labour			100.000frs
	TOTAL			338.250



MOLA FAKO & SONS CONSTRUCTION COMPANY LTD

SERVICES OFFERED: General Construction, Renovation, Plan Drawing, Consultancy, Site Plan Development, Building Permit and Land Certificate follow up

HEAD OFFICE: Lady L. Street - Untarred Malingo - Molyko – Buea

Tel: (237) 654 992 525/672 259 888

E-Mail: mola

11C) PLUMBING WORK (INSTALLATION)

No	Description	Qty	Unit Price	Amount
1	Toilet pot	5	35000frs	175.000frs
2	Wash hand basin with stand	5	18.000frs	90.000frs
3	Toilet roll holder	5	2.500frs	12.500frs
4	Mirror	5	5.000frs	25.000frs
5	Soap dish	4	1.500frs	6.000frs
6	Towel hanger	4	5.000frs	20.000frs
7	Basin screw	5	1.000frs	5.000frs
8	Kitchen tap	1	12.000frs	12.000frs
9	Wash basin tap	5	3.000frs	15.000frs
10	Shower tap	5	2.500frs	12.500frs
11	Telephone shower	4	8.000frs	32.000frs
12	Brass tap ½ inch	4	2.500frs	10.000frs
13	Flex pipe female/female	12	1500frs	18.000frs
14	Teflon	15	500frs	7.500frs
15	Camping gas	2	1000frs	2.000frs
16	PVC reducer 63/40	4	500frs	2.000frs
17	Double kitchen sink	1	25.000frs	25.000frs
18	PVC elbow 40	4	500frs	2.000frs
19	PVC pagofor gum	1	9.000frs	9.000frs
20	Normalize pipe 40	1	3.000frs	3.000frs
21	Galba join	2	3.500frs	7.000frs
22	Brass socket ½ inch	10	500frs	5.000frs
23	Brass nipple ½ inch	10	500frs	5.000frs
24	Brass male/female	10	500frs	5.000frs
25	Peck with screw	3	1500frs	4.500frs
	Cost of material			507.000frs
	Labour			200.000frs
	TOTAL			707.000frs



MOLA FAKO & SONS CONSTRUCTION COMPANY LTD

SERVICES OFFERED: General Construction, Renovation, Plan Drawing, Consultancy, Site Plan Development, Building Permit and Land Certificate follow up

HEAD OFFICE: Lady L. Street - Untarred Malingo - Molyko – Buea

Tel: (237) 654 992 525/672 259 888

E-Mail: mola

SUMMARY

1)	FOUNDATION	4.183.800frs
2)	ELEVATION	5.278.700frs
3)	ROOFING	3.615.000frs
4)	ELECTRICAL WORK	966.000frs
5)	CEILING	619.500frs
6)	WOOD WORK	969.000frs
7)	METAL WORK	529.000frs
8)	TILING	2.113.095frs
9)	DOCORATION	525.000frs
10)	PLASTERING	1.300.220frs
11A)	PLUMBING WORK (PIPPING)	375.000frs
11B)	PLUMBING WORK (INTERNAL PIPPING)	707.000frs
11C)	PLUMBING WORK (INSTALLATION)	338.250frs
	GRAND TOTAL	16.768.565FRS

Note: Materials are cost as per the level of the town with transportation exclusive as it is the sole responsibility of the site supervisor.

Done By: Fako Samuel

Tel: (237) 654 992 525/672 259 888